## LOAN DOCUMENT

ER	PHOTOGRAPH THIS	SHEET
N NUMB	LEVEL	INVENTORY
DTIC ACCESSION NUMBER		
OTIC AC	DOCUMENT IDENTIFICATION	
		• ••
	DISTRIBUTIO	ON STATEMENT
TIS GRAM U		
TIC TRAC LINANNOUNCER [] USTIFICATION	<b>.</b>	
STRIBUTION/		
AILABILITY CODES ISTRIBUTION AVAILABILITY AND/O	R SPECIAL	
		DATE ACCESSIONED
D-1		
17 1		
DISTRIBUTION STAN	MP	
	Reproduced From	
	Best Available Copy	DATE RETURNED
	<del></del>	DATE RETURNED
1998′	1223 012	
DA	TE RECEIVED IN DTIC	REGISTERED OR CERTIFIED NUMBER
	PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-FE	DAC
IC FORM 70A	DOCUMENT PROCESSING SHEET	PREVIOUS EDITIONS MAY BE USED UNTIL

UNCLASSIFIED

NO DISTRIBUTION STATEMENT

NADC Tech. Info.

APPENDIX 7
SYSTEM MANAGEMENT 2
FINAL SOFTWARE REPORT
DATA ITEM NO. A005

# INTEGRATED ELECTRONIC WARFARE SYSTEM ADVANCED DEVELOPMENT MODEL (ADM)

PREPARED FOR:

NAVA AIR DEVELONMENT JENTER

VARMINSTER, PENNSYEVANIA

CONTRACT N62269-75-C-0070

RAYTHEON

ELECTROMAGNETIC

1 OCTOBER 1977

UNCLASSIFIED

#### APPENDIX 7

#### SYSTEM MANAGEMENT DESIGN SPECIFICATION FINAL SOFTWARE REPORT DATA ITEM A005

# INTEGRATED ELECTRONIC WARFARE SYSTEM (IEWS) ADVANCED DEVELOPMENT MODEL (ADM)

Contract No. N62269-75-C-0070

#### Prepared for:

Naval Air Development Center Warminister, Pennsylvania

#### Prepared by:

RAYTHEON COMPANY
Electromagnetic Systems Division
6380 Hollister Avenue
Goleta, California 93017

**1 OCTOBER 1977** 

The second secon	
- Commence of the Commence of	
DAVT	
RAYI	HEON )
<b>7.11.11</b>	

CODE IDENT NO. 49956

SPEC NO. 53959-GT-0757

SHEET of 24

REV

	1	A THE STREET		and the same	 
TYPE	OF	SPEC			

TI					

A

			COM	PUT S	`ER YST	SUI EM	BPI M	RO(	GRA AGI	AM : EME	DESI NT	[GN 2,	I DO	OCU VS	J <b>M</b> 1	ENT	Γ,						
FUNCTION	· · · · · · · · · · · · · · · · · · ·	AP	PROVED			Т	D.	ATE		FUNC	TION	<u> </u>			APPE	OVE	D	<del> ,</del>		Т	DA	TE	
WRITER	Thon	urs	, L.CK	t LAir	isoll.	11/1	40	đ j	76												* *************************************		
	<del> </del>		<del>,</del>		()	-														-		<del>-</del>	
											,						•,						
										SIONS													
СНК		DE	SCRIPTI	ON					REV	снк		•		DE	SCR	PTI	N					F	₹E
																		٠		• ,			
				1																			
																					•		
PEVISION	. [		1	T	T		Τ	T	1			<u> </u>	· 	<u> </u>	<del>.</del>			· 	Τ			$\overline{}$	_

REVISION SHEET NO. REVISION REV STATUS OF SHEETS SHEET NO.



49956

spec no. 53959-GT-0757

SHEET 2 of 24

REV

#### 1.0 SCOPE

#### 1.1 IDENTIFICATION

This document describes the implementation of the System Management 2 (SM2) Functional Group of the SC Operational Software resident in Resource Management Processor (RMP).

#### 1.2 SUBPROGRAM TASKS

#### 1.2.1 System Management 2 Driver

SMDR shall have the responsibility of decoding System Management 1 (SM1) messages passed to it from the RMP Executive. It shall then call the appropriate SM2 processing routine.

#### 1.2.2 Overflow Message Processing

SMOFP shall process the SM1 messages resulting from Sorter Throttle Files Full and Sorter Track Files Full messages.

#### 1.2.3 Threshold Control Processing

SMTHR and SMTHI shall process the SM1 messages resulting from Sorter IB  $\geq 3/4$  Full and IB  $\leq 1/4$  Full messages, respectively.

#### 1.2.4 Aircraft Parameters Processing

SMACP shall process the RMP-Executive-origined request for an Aircraft Parameters update. It shall interrogate the Inertial Navigation System (INS) and distribute the INS data to the common data base and the Parameter Encoder (PE).



code ident no. 49956 SPEC NO. 53959-GT-0757 SHEET

3 of 24

REV

#### 2.0 APPLICABLE DOCUMENTS

The following documents, of the exact issue shown, form a part of this specification to the extent specified herein. In the event of conflict between the documents referenced herein and the contents of this specification, the contents of the Computer Program Design Specification for the Integrated Electronic Warfare System (IEWS) Advanced Development Model (ADM) Program shall be considered superseding requirements.

#### 2.1 COMPUTER PROGRAM PERFORMANCE SPECIFICATION

Computer Program Performance Specification for the Integrated Electronic Warfare System (IEWS) Advanced Development Model (ADM) Program (U), Raytheon Company, Electromagnetic Systems Division, (Number 061290529), (date 1 June 1976), (classification U).

#### 2.1.1 Applicable CPPS Paragraphs

Module Name	CPPS Paragraph
System Management 2 Driver	Not specified explicitly
Overflow Processing	3.3.7.2
Threshold Control	3.3.7.1
Aircraft Parameters	3.3.7.3

#### 2.2 COMPUTER PROGRAM DESIGN SPECIFICATION

Computer Program Design Specification for the Integrated Electronic Warfare System (IEWS) Advanced Development Model (ADM) Program (U), Raytheon Company, Electromagnetic Systems Division, (number 53959-GT-0750), (date TBD), (classification U).

#### 2.3 DATA BASE DESIGN DOCUMENT

The Common Data Base Design Document, System Controller Unit, IEWS, ADM, Document No. 53959-GT-0751, shall apply to this subprogram.



CODE IDENT NO.

49956

CUEET

SPEC NO.

SHEET 4 OF

REV

#### 2.4 MISCELLANEOUS DOCUMENTS

The following documents shall apply to this subprogram:

Document No.	Document Title
53959-GT-0756	Computer Subprogram Design Document, Executive, IEWS
53959-JK-1002	Interface Control Document, System Controller - Sorter
53959-GT-0759	Computer Subprogram Design Document, Data Extraction, IEWS
53959-NJK-0200	Unit Hardware Development Specification, Parameter Encoder, IEWS
TBD	STE Software Document
WS-8506 Revision 1,	Requirements for Digital Computer Program Documentation



49956

53959-GT-0757

SHEET
5 of 24 REV

3.0 REQUIREMENTS

#### 3.1 SUBPROGRAM DETAILED DESCRIPTION

#### 3.1.1 System Management 2 Driver (SMDR)

SMDR shall be the driver routine of the SM2 Functional Group. The Exec shall pass to SMDR one of the following in the X-register:

- 1) The value Ø
- 2) A pointer to a SM1 message

If the X-register contains  $\emptyset$ , the Aircraft Parameters Routine (SMACP) shall be called to (1) update the common data base image of the following:

INS Variable	Common Data Base Item
Aircraft Heading	SYHDC
Altitude	SYALC
Pitch	SYPTC
Roll	SYROC

and (2) update the azimuth correction field of the SC-to-PE Interface.

If the X-register is non-zero, SMDR shall use it as a pointer to retrieve the Sorter Op-code from the SM1 message (see Figure 3). The Op-code shall be fetched from the left byte of SOS1. X'89' shall then be subtracted fromthe Op-code to compute an index, i. This index, which exists only in the A-register, shall be verified to be in the range  $\emptyset \le i \le 3$ . If i is out of range, control shall be transferred to label SMD8 $\emptyset$ , where an instrumentation message is sent to the EXEC. Control shall then be returned to the EXEC. If i is in the specified range, the value of i (A-register) shall be added to the address of the SM2 processing table (SM2PT) and the result stored in the B-register. The effective address



49956

SHEET

SPEC NO.

REV

(B-register) shall be used indirectly to call one of the SM2 processing routines, whose list of symbolic names constitute SM2PT. All of the processing routines shall be passed the same data:

- 1) The address of the SM1 message word  $\emptyset$  in the X-register.
- 2) The contents of the right byte of the Op-code word in the A-register. (This right byte may be the SFN).

After the individual message processing routine has completed its task, control shall be returned by SMDR to the EXEC.

#### 3.1.2 Overflow Message Processing (SMO FP)

The function of SMOFP shall be partially implemented in the priority 1 SC software. This routine is called by the driver to process SM1 messages derived from the Sorter Track Files Full and Sorter Throttle Files Full messages. In the case of Track File Overflow, the complete implementation would:

- 1) Search the Emiter Track File for a 'deletable' emitter.
- 2) Send a Create File message to the Sorter (overwriting the existing Sorter Track File).
- 3) Process the overflow emitter as a new emitter.

Throttle File Overflow processing has not been specified explicitly in the CPPS.

In the priority 1 implementation, SMOFP shall receive from the driver a pointer to the SOMNO word of the SM1 message in the X-register (See Figure 3), and the Sorter File Number (SFN) in the A-register. The priority 1 version of SMOFP shall simply send the Sorter Overflow message data to Data Extraction (see Data Extraction CSDD). Control shall then be returned to the driver.



code ident no. 49956 SPEC NO.

SHEET 7 OF

REV

#### 3.1.3 Threshold Control Processing (SMTHR)

The function of SMTHR shall be partially implemented in the priority 1 SC software. This routine shall be called by the driver to process SM1 messages derived from Sorter IB≥3/4 Full messages (processed by SMTHR) or Sorter IB≤1/4 Full messages (processed by SMTHI). This routine would decrement (SMTHR) or increment (SMTHI) the value of the encoding threshold and if the new value was in the specified range, it would be saved in the Common Data Base as SYTHC and the encoding threshold field in the SC-to-PE Interface would be updated. (See Parameter Encoder Unit Hardware Specification). However, in the priority 1 implementation, no data is transferred to the Common Data Base or the PE. As implemented, SMTHR (SMTHI) shall receive from the driver, a pointer to the SOMNO word of the SM1 message in the X-register (See Figure 3) and the SFN in the A-register. SMTHR (SMTHI) shall then retrieve the current value of the encoding threshold (SYTHC) from the common data base. The decremental (incremental) value (SYTHV) shall be subtracted from (added to) to the current value of the threshold. If the difference is less than the lower limit SYTHL (sum is greater than the upper limit SYTHU), processing shall continue at label SMT99. Otherwise, processing shall continue at label SMT8\( \text{0}. \) In the priotity 1 implementation, SMT8Ø shall simply pass control to SMT99.

#### 3.1.3.1 SMT99

At label SMT99, control shall be returned to the SM2 driver.

#### 3.1.4 Aircraft Parameters Processing (SMACP)

The function of SMACP shall be partially implemented in the priority 1 SC software. This routine shall be called by the driver in response to an aircraft parameter update request from the RMP. This routine shall interrogate the Inertial Navigation System (INS) to obtain the current value of aircraft heading altitude, pitch, and roll. This data shall be stored in the common data as SYHDC, SYALC, SYPTC, and



code ident no. 49956

SHEET 8 OF

SPEC NO.


REV


SYROC, respectively. The INS function in the priority 1 implementation shall be supplied by the STE software (See STE software document). The azimuth correction factor shall then be computed by adding the new current value of aircraft heading (SYHDC) to the antenna boresight bearing constant (SYBAC). The sum shall be stored in the common data base as SYFAC, the azimuth correction factor. Subroutine SMPEU shall than be called to update the SC-To-PE Interface (See Figure 1).

Additional processing not included in the priority 1 implementation would then be performed. This would include a check for excessive pitch or roll. If either is excessive and the Sorter NESU processor is in the active state (processing PDW's), the NESU would be placed in the inactive state (via an SC-to-Sorter message). If the value of both pitch and roll are acceptable and the NESU is not active, it would be activated (via an SC-to-Sorter message). In all cases, control shall then be returned to the SM2 driver.


#### 3.1.4.1 SMPEU


SMPEU shall compute the value of the data word to be stored in the SC-to-PE Interface. The format of this data word is shown in Figure 1. SMPEU shall retrieve the value of the azimuth correction factor (SYFAC) from the common data base and combine it with the current value of the encoding threshold (SYTHC). This data word shall then be sent to the PE (via address X'F206'). Control is returned to the calling routine.





SORTER OVERFLOW PROCESSING TLC 27 AUG 76







THRESHOLD CONTROL
(INCREMENT)

TLC 27 AUG 76


SHT ROFR



1 OF 2



A/C PARAMETERS ROUTINE
TLC 14 SEP 76
2 OF 2



UPDATE SC-TO-PE INTERFACE
4 OCT 76 TLL



## RAYTHEON COMPANY

LEXINGTON, MASS, 02173

CODE IDENT NO.

49956

SHEET 16 of

SPEC NO.

REV

- COMPUTER SUBPROGRAM ENVIRONMENT 3.3
- 3.3.1 Tables
- System Management 2 Driver Table 3.3.1.1

SM2 Processing Table (SM2PT)

Purpose and Type - Fixed length table containing the addresses of the subroutines called by the SM2 driver to process SM1 messages.

Size and Indexing Procedure - Four (4) entries of one (1) 16-bit word. All entries shall be referenced by indexed displacement from the start of the table.

#### Entry Format

15

Routine Address

Field	Description	Units	LSB
Routine Addr	Address of a SM2 processing routine	N/A	N/A

#### 3.3.2 Variables

There shall be no local variables associated with the SM2 Functional Group.

#### 3.3.3 Constants

There shall be no local constants associated with the SM2 Functional Group.



code ident no. 49956 SPEC NO.

SHEET 7 OF

REV

3.3.4 Flags

There shall be no local flags associated with the SM2 Functional Group.

- 3.3.5 Indices
- 3.3.5.1 System Management 2 Driver Indices

SM2 Processing Table Index

a. Index Name:

i (not a symbolic label)

b. Purpose:

This index shall be used to fetch a

SM1 message processing routine address

from table SM2PT.

The index shall assume the following range of values:  $0 \le i \le 3$ .

#### 3.3.6 Common Data Base References

The following items in the common data base are referenced by the routines in the SM2 Functional Group:

CDB Symbol	Reference	ing Routine		Desc	ription	
SYTHU	SMTHR,	SMTHI	Encoding	thres	hold upp	er limit
SYTHL	11	11	tt	***	low	ver limit
SYTHC	11	11	11	11	cur	rent value
SYTHV	**	11	11	*1		remental/ cremental value
SYHDC	SMACP		Current	value o	of aircra	aft heading
SYALC	11		11	11	11	altitude
SYPTC	11		11	11	**	pitch
SYROC	**		11	11	ŤŤ	roll
SYFAC	. 11		11	11	azimu	th correction factor
SYBAC	11		Antenna	boresi	ght bear	ring constant



CODE IDENT NO.

49956

SHEET 18 of

SPEC NO.

REV

#### 3.4 INPUT/OUTPUT FORMATS

#### 3.4.1 Input

The format of the input SM1 messages shall be as specified in the Common Data Base Design Document 53959-GT-0751 (See Figure 3).

#### 3.4.2 Output

The format of the output instrumentation data shall be as specified in the Data Extraction CSDD,

The format of the data output to the SC-to-PE Interface shall be as specified in the Parameter Encoder Unit Hardware Development Specification. The field definition of this interface is shown in Figure 1.

#### 3.5 SYSTEM LIBRARY SUBROUTINES

There are no system library subroutines required by the SM2 Functional Group.

#### 3.6 CONDITIONS FOR INITIALIZATION

This subprogram shall have unconditional entry and shall require no special initialization procedure.

#### 3.7 SUBPROGRAM LIMITATIONS

The SM2 Functional Group makes the following assumptions:

If SMDR is processing a SM1 message (Sorter derived), the only Sorter message Op-codes processed shall be X'89', X'8A', X'8B', and X'8C'. All others shall result in an error alert message being sent to Data Extraction.



CODE IDENT NO.

49956

SHEET


SPEC NO.

19 of

REV

#### 3.8 INTERFACE DESCRIPTION

The SM2 driver shall be called by the RMP EXEC. The driver then shall then call one of the SM2 processing routines (SMACP, SMTHI, SMTHR, or SMOFP). Instrumentation shall be called as required for data extraction and is not shown on the diagrams.



INTERFACE DESCRIPTION

SYSTEM MANAGEMENT 2
TLC 15 SEP 76



CODE IDENT NO. 49956

SPEC NO.

21 OF

REV

0	
<b>7-4</b>	
2	
က	
4	
5	ACOR
9	Ŧ
7	
8	
6	ESH
10	THRESH
11	
12	
13	LP
14	T
15	$\times$

		25					
LSB	TBD	1.6	n		· ·	Marie - 100	
Units	TBD	dB Degrees,	CW, wrap- around at X'FF'				
Description	Long Pulse Modes	Encoding Threshold Angle Correction Data					
Field	LP	THRESH ACOR					

Figure 1. SC-To-PE Interface

				200	~
	A	YT	H	ΞO	N
Complete on the					

CODE IDENT NO. SPEC NO.

49956
SHEET
22 OF REV

f .	t i	1	1	1	ĺ	1	t i				ł '	Ì	ł	1 1	
1	,			1	Į	i i				ł	T .	}			1
1 =	4.4	40	10	44	10	0	0	7	C		1	9	9	1 1	Λ
1 19	14	10	12	1 11	IIU	9	0	1 6	U	เ	4	J	4	1	U
					1	<u> </u>		L		<u> </u>	1	<del>!</del>		L	

Word Ø	ø	HDG
1	AL	Т
2	PIT	СН
3	ROI	LL

Field	Description	Units	LSB
HDG	Aircraft Heading	Degrees, increasing CW, wrap-around at X'FF'	1.40625
ALT	Aircraft Altitude	Feet	1øø
PITCH	Aircraft Pitch	TBD	TBD
ROLL	Aircraft Roll	TBD	TBD

Figure 2. INS-to-SC Interface

									Ą									
(RA)	F	RAYTHEON COMPANY							49956			SPEC NO. SHEET						
IIA					LI	EXING.	TON, M	ASS. 0	2173		43			23			REV	
		15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	1
Word				1.0	-2			<u> </u>	<u> </u>				<u> </u>	1	L	1		_   
., 0 2 0	Ø				· · · · · · · · · · · · · · · · · · ·	 	t .	SC	MN	0				· 				_  _
	1							SC	NW									
	2			*********				SC	os1									
	3					1		S	OS2					1				
				-				SC	) S 3									
	4	<u> </u>				<u> </u>								<u> </u>				<u> </u>
	5					1		S(	OS4			·		<u> </u>				_
	6	L				<u> </u>		S	O S 5	1				I .				
	7		•					S	OS6									
	8		SOS7															
	9	\						S	 S8					T				=
						T								<del></del>				<u> </u>
	10		SOS9															
	11							S	os1	Ø								
,	12						······································	N	от	USI	ΞD			[				
	12						· · · · · · · · · · · · · · · · · · ·	N	ОТ	USI	E D			1				

Figure 3a. System Management 1 Message (from CP)



CODE IDENT NO.

49956

53959-GT-0757 SHEET 24 of 24 REV

Field	Description	Units	LSB
SOMNO	Message number ( = TBD)	Ņ/A	1
SONW	Number of words in message	N/A	1
SOS1	Sorter message word 1 (Op-Code,	et¢) ''	N/A
SOS2	2	77	11
SOS3	3	11	11
SOS4	4	**	11
SOS5	5	11	11
SOS6	6	11	11
SOS7	7	**	11
SOS8	8	77	11
SOS9	9	11	11
SOS10	10	N/A	N/A
	•		
			e.

Figure 3b. System Management 1 Message (from CP)